

**RRAS Provider/SCED Generator Rate 16th May 2021 to 15th Jun 2021 (Region-wise)**

Sl No	RRAS Provider Name	Region	Installed Capacity (MW)	Fixed cost (Paisa/kWh)	Variable cost (Paisa/kWh)	Ramp Up (MW/Block)	Ramp Down (MW/Block)	Technical Minimum (MW)
1	AGBPP - Kathalguri	NER	291	222.50	123.50	34	34	156
2	AGTPP - Agartala	NER	130	150.70	173.00	10	10	69
3	BongaigaonTPP	NER	750	240.63	294.70	103	103	375
<b>Total Installed Capacity</b>			<b>1,171</b>					
<a href="http://www.nerpc.nic.in/Ancillary%20Service.php">Source- NERPC-http://www.nerpc.nic.in/Ancillary%20Service.php</a>								
4	Darlipali STPP	ER	800	211.50	109.80	113	113	413
5	Talcher STPS - I	ER	1,000	95.90	190.20	140	140	511
6	Kahalgaoon STPS - II	ER	1,500	108.90	202.60	211	211	773
7	Kahalgaoon STPS - I	ER	840	104.80	213.70	115	115	421
8	NPGC	ER	660	253.90	216.90	93	93	340
9	Maithon Power Limited	ER	1,050	142.30	219.50	148	148	541
10	Nabinagar Thermal Power Project (BRBCL)	ER	750	250.00	233.90	103	103	413
11	Farakka STPS - III	ER	500	149.20	264.40	70	70	258
12	Farakka STPS - I & II	ER	1,600	82.40	269.30	224	224	820
13	MTPS Stage-II	ER	390	273.40	274.40	53	53	195
14	Barh TPS	ER	1,320	184.00	278.90	186	186	681
<b>Total Installed Capacity</b>			<b>10,410</b>					
<a href="http://erpc.gov.in/as-3-formats">Source- ERPC-http://erpc.gov.in/as-3-formats</a>								
15	Rihand TPS Stage - III	NR	1,000	144.30	135.70	141	141	516
16	Rihand TPS Stage - II	NR	1,000	70.40	137.50	141	141	516
17	Rihand TPS Stage - I	NR	1,000	84.40	137.80	138	138	506
18	Singrauli STPS	NR	2,000	65.50	139.30	279	279	1,022
19	Anta Gas Power Project GF	NR	419	70.90	191.10	63	63	225
20	Dadri Gas Power Project GF	NR	830	57.70	203.80	50	50	456
21	Auraiya Gas Power Project GF	NR	663	63.50	216.80	138	138	365
22	Tanda TPS Stage-II	NR	660	160.30	261.60	94	94	342
23	Dadri TPS Stage - I	NR	840	97.30	299.60	115	115	422
24	Unchahar TPS Stage - IV	NR	500	155.90	300.00	71	71	258
25	Dadri TPS Stage - II	NR	980	143.70	303.20	139	139	508
26	Unchahar TPS Stage - I	NR	420	108.10	318.30	58	58	210
27	Unchahar TPS Stage - III	NR	210	134.70	318.30	28	28	105
28	Unchahar TPS Stage - II	NR	420	100.90	321.10	56	56	208
29	Indra Gandhi STPS	NR	1,500	161.50	336.90	212	212	778
30	Dadri Gas Power Project CRF*	NR	830	57.70	587.60	50	50	456
31	Anta Gas Power Project RF	NR	419	70.90	624.00	63	63	225
32	Dadri Gas Power Project RF	NR	830	57.70	658.00	50	50	456
33	Auraiya Gas Power Project RF	NR	663	63.50	843.20	138	138	365
34	Dadri Gas Power Project LF	NR	830	57.70	1,246.50	50	50	456
35	Auraiya Gas Power Project LF	NR	663	63.50	1,271.60	138	138	365
36	Anta Gas Power Project LF	NR	419	70.90	1,276.10	63	63	225
<b>Total Installed Capacity</b>			<b>12,442</b>					
<a href="http://www.nrpc.gov.in/comm/ancillaryservices.html">Source- NRPC - http://www.nrpc.gov.in/comm/ancillaryservices.html</a>								
37	Talcher STPS - II	SR	2,000	71.40	191.40	281	281	1,031
38	Neyveli New Thermal Power Project (NNTPP)	SR	1,000	180.40	219.90	141	141	516
39	Ramagundam STPS - III	SR	500	76.80	242.60	70	70	258
40	NLC TPS - I Exp	SR	420	96.50	242.80	58	58	250
41	Ramagundam STPS - I & II	SR	2,100	72.80	247.40	293	293	1,074
42	NLC TPS - II Exp	SR	500	230.90	253.70	68	68	293
43	NLC TPS - I	SR	630	71.00	264.00	85	85	369
44	NLC TPS - II	SR	840	73.60	264.00	113	113	491
45	Simhadri STPS - II	SR	1,000	152.00	294.10	141	141	518
46	Simhadri STPS - I	SR	1,000	94.20	297.20	141	141	518
47	NTPL - Tuticorin TPS	SR	1,000	155.30	301.40	150	150	518
48	NTECL - Vallur TPS	SR	1,500	177.50	328.60	211	211	773
49	Kudgi STPS I	SR	2,400	166.80	360.20	338	338	1,238
<b>Total Installed Capacity</b>			<b>14,890</b>					
<a href="http://www.srpc.kar.nic.in/html/all_uploads.html">Source- http://www.srpc.kar.nic.in/html/all_uploads.html</a>								
50	Korba STPS STG ( III)	WR	500	138.40	128.20	70	70	258
51	Korba STPS STG ( I & II)	WR	2,100	68.59	130.70	293	293	1,074
52	Sasan Power Ltd	WR	3,960	16.80	135.10	180	180	2,400
53	SIPAT TPS Stg-I	WR	1,980	130.39	140.10	278	278	1,021
54	Vindhyachal-IV	WR	1,000	156.51	144.40	140	140	516
55	SIPAT TPS Stg-II	WR	1,000	123.82	144.50	141	141	516
56	Vindhyachal-III	WR	1,000	104.56	146.30	140	140	516
57	Vindhyachal-II	WR	1,000	70.06	147.60	140	140	511
58	Vindhyachal-V	WR	500	167.17	149.00	70	70	255
59	Gandhar Gas Power Project GF	WR	657	105.91	151.70	293	293	354
60	Kawas Gas Power Project GF	WR	656	83.94	152.20	50	50	352
61	Vindhyachal-I	WR	1,260	85.56	153.10	172	172	631
62	Gandhar Gas Power Project NAPM	WR	657	105.91	159.00	293	293	354
63	Kawas Gas Power Project NAPM	WR	656	83.94	159.70	50	50	352
64	Costal Gujarat Power Ltd	WR	4,150	90.08	168.11	150	150	2,090
65	Ratnagiri Gas & Power Pvt Ltd GF*	WR	664	119.00	181.00	300	300	354
66	LARA	WR	1,600	167.36	207.10	225	225	825
67	NTPC-SAIL Power Company Pvt. Ltd	WR	500	170.30	238.90	68	68	250
68	Mouda STPP Stage-I	WR	1,000	187.80	267.80	141	141	516
69	Ntpc khargone unit 1	WR	1,320	181.27	269.70	186	186	681
70	Gadarwara STPP St-I	WR	1,600	207.72	274.10	225	225	825
71	Mouda STPP Stage-II	WR	1,320	148.49	292.10	186	186	680
72	Solapur Super Thermal Power Project	WR	1,320	172.05	348.50	185	185	681
73	Ratnagiri Gas & Power Pvt Ltd RF*	WR	1,122	119.00	357.00	300	300	354
74	Ratnagiri Gas & Power Pvt Ltd IR	WR	540	119.00	369.00	300	300	288
75	RGPPPL-Maharashtra	WR	68	119.00	405.00	300	300	36
76	RGPPPL-Others	WR	32	119.00	405.00	300	300	17
77	Gandhar Gas Power Project RF	WR	657	105.91	594.80	293	293	354
78	Kawas Gas Power Project RF	WR	656	83.94	598.50	50	50	352
79	Kawas Gas Power Project LF	WR	656	83.94	1,609.40	50	50	352
<b>Total Installed Capacity</b>			<b>30,186</b>					
<a href="http://www.wrpc.gov.in/Commercial_rras_dat.asp?ln=e">http://www.wrpc.gov.in/Commercial_rras_dat.asp?ln=e</a>								
<b>All India Total Installed Capacity</b>			<b>69,099</b>					

\*Details mentioned are as per previous AS3 Format (Charges yet to submit by plant for period 16th May 2021 to 15th Jun 2021 )